



- Comments:
1. Insulation to be bonded to deck or adhered vapour retarder a minimum of 122 cm (4') out from wall/curb with approved Lexcan adhesive or insulation adhesive, applied according to manufacturer's directions (adhesive must be approved by Lexcan).
 2. Membrane to be fully adhered down wall/curb and out a minimum 30 cm (12") onto insulation or deck.



**Flatbond™ Method for Ballasted Roof System
(AAI Method)
Roofing System Detail**

Scale: Not to scale
Date: August, 2016
Detail No.: L-B-102